

# AMZAIR

monobloc premium heat pumps

## Installation and Commissioning Procedure



**OPTIM'** (heating)

**& OPTIM' DUO**

(heating and domestic hot water  
production)

---

### ASHP monobloc indoor

OPTIM' and OPTIM'DUO 4kW single phase

OPTIM' and OPTIM'DUO 6kW single phase

OPTIM' and OPTIM'DUO 9kW single phase

*07/04/2018 version*



HEATING, COOLING AND DOMESTIC HOT WATER

TABLE OF CONTENTS

1-	ASHP and ancillary equipments Overall view .....	4
1-1	Grid .....	4
1-2	Air duct .....	4
1-3	ASHP .....	4
1-3-1	PAC heating only .....	4
1-3-2	PAC Duo .....	4
1-3-3	Equipements packaging view .....	6
1-4	Thermostats .....	7
1-4-1	DELTA DORE TH RA .....	7
1-4-1	DELTA DORE TYBOX 5100 and receptor RF6200 ( <i>Option</i> ) .....	7
1-4-2	DELTA DORE TH FI ( <i>Option</i> ) .....	7
1-5	Tank Kits .....	7
1-5-1	Integrated tank (OPTIM' 4 and 6 kW) .....	7
1-5-2	Separated tank (OPTIM' 4, 6 and 9 kW) .....	7
1-6	Separated distribution water kit .....	8
1-6-1	Not mixed zone .....	8
1-6-1	Two zones, one unmixed .....	8
2-	INSTALLATION PHASES DESCRIPTION .....	9
2-1	Grid installation .....	10
2-2	Air duct installation .....	10
2-3	ASHP installation in site .....	10
2-4	Hydraulic connections .....	13
2-5	Electrics connections .....	14
2-5-1	Connecting the power network .....	14
2-5-2	Sensor temperature connections .....	15
2-5-3	Sub zone 2 ways valves connection and sub zone water pumps connection (water distribution separated from the ASHP) .....	15
2-5-4	Thermostats connection .....	16
3-	Start-up steps .....	19
3-0	ASHP Control panel & screen terminal function and mode .....	20
3-1	ASHP Power on .....	21
3-2	TYBOX thermostat radio synchronization .....	21
3-2	The 2 Ways valves set-up and commissioning (sub-zone) .....	21
3-3	Manual mode to purge the water circuit and test water flow efficiency: 1 à 3 zone(s) direct(s) .....	23
3-3-1	Valves start .....	23
3-3-2	ASHP Water pump start .....	24

3-3-3 Test of water flow efficiency and water circuit purge ..... 24

3-3-4 Water set point and set point adjustment..... 25

3-3-5 Temperature sensors start and control ..... 26

3-4 Manual start to purge the water circuit and test of water flow efficiency : 2 ou 3 zones including 1 or 2 mixed ..... 28

3-4-1 Manually start the 3 and 2 ways valves ..... 28

3-4-2 Water pumps start..... 29

3-4-3 Test of water flow efficiency, and circuit purge..... 29

3-4-4 Define water set points and set points ..... 30


3-4-5 Temperature sensors start and control ..... 31

Annex : commissioning and acceptance document..... 32

Annex : alarms code table..... 34


## 1- ASHP AND ANCILLARY EQUIPMENTS OVERAL VIEW

### 1-1 Grid



X 1


Grid + mounting brackets



X 8


ISO 4017 M6\*20 screw + M6 washer

### 1-2 Air duct



X 1

Air duct + fixing hooks + rivet nut for fixing brackets



X 2

Air duct top and bottom frames




X 2

Air duct side frames


### 1-3 ASHP

#### 1 3-1 PAC heating only

#### OPTIM 4 and 6 kW




#### OPTIM 9 kW



X 10


Screw DIN7991 M6\*40  
body panel fixation screws



X 10

Screw DIN7991 M6\*40  
body panel fixation screws

**OPTIM 4 and 6 kW**




**X 10**

Screws DIN7991 M6\*40



body panel fixation screw





**X 4**

Flat head, slotted drive screws M6\*20



body panel fixation screw

**OPTIM 9 kW**



**X 10**

Vis DIN7991 M6\*40



body panel fixation screws

1-3-3 Equipements packaging view

**OPTIM 4 et 6 kW**




+ If OPTIM DUO



 Caution: Have a 19 mm spanner to unscrew the tank to the delivery palette.

**OPTIM 9 kW**



+



Grid and air duct

+ if OPTIM DUO

Tank 200L or 300L



PAC + Tank kit + water distribution kit (if separated water distribution)

\*DHW tank :

- If integrated: 170L or 200L
- If separated : 170L, 200L or 300L

**1-4 Thermostats**

1-4-1 DELTA DORE TH RA



X number of zone

1-4-1 DELTA DORE TYBOX 5100 and receptor RF6200 (Option)



X number of zone

1-4-2 DELTA DORE TH FI (Option)



X number of zone

**1-5 Tank Kits**

1-5-1 Integrated tank (OPTIM' 4 and 6 kW)



X 1

Copper outlet tube for DHW



Gaskets are not provided



X 1

Copper inlet tube (2 parts) + Hose DN20 1m female connector 3/4 "



Gaskets are not provided



X 1

Security unit 3/4 "



X 1

Security unit siphon



X 1

DHW temperature sensor 6 m

1-5-2 Separated tank (OPTIM' 4, 6 and 9 kW)



X 1

Security unit 3/4 "



X 1

Security unit siphon



X 1

DHW temperature sensor 6 m

**1-6 Separated distribution water kit**

1-6-1 Not mixed zone



2 ways valve


+



Actuator 2 ways valve+ fixing ring  
(see page 15 for electric connection)

X number of zone

1-6-1 Two zones, one unmixed



Mixed zone kit

X 1

see page 15 for electric connection



2 ways valve


+



Actuator 2 ways valve + fixing ring  
(see page 15 for electric connection)

X 1

**2 WAYS VALVE ACTUATOR SET-UP**



## 2- INSTALLATION PHASES DESCRIPTION

N°	Main installation phases
1	Grid installation inside the wall
2	Air duct installation on the grid
3	Installation of the ASHP on its footprint
4	Hydraulic connection
5	Electric connection

### Hardware part list to be provided for the project

#### Hydraulic hardware parts procurement list and project recommendations

- ASHP and DHW tank shut off valves + flexible pipe between ASHP output and input and the heating installation (to improve installation acoustic)
- Isolated heating pipework 3/4" diameter (internal diameter of 20 mm minimum, including elbow pipe, flexible pipes, valves...) for OPTIM'4 et 6kW and 1" diameter (internal diameter of 26 mm minimum, including elbow pipe, flexible pipes, valves...) for OPTIM'9kW
- **Mandatory minimum installation water volume for appropriate operation: 30L for 4kW / 45L for 6kW / 65L for 9 KW + and at the minimum of 30% of the emitters running at all the time<sup>(1)</sup>**

If it is not the case (example: head thermostatic radiator valves) = mixing bottle water (25L mini for 4kW / 40L mini for 6kW / 60L for 9Kw) <sup>(2)</sup> Or differential pressure valve + ASHP double service and/or back-up electric heater.

- Shut-off valve + installation filling valve + automatic air vent shut-off cock (on every high point of the circuit including the mixing bottle in the separated version)
- Mandatory magnetic system filter on each circuit of the installation. (in option : integrated system filter)
- Drain siphon for the condensate evacuation
- Mandatory water cleaning before installation filling (following DTU or the local code of practice guidelines)
- Heating water chemical treatment (to prevent scale, oxygen corrosion, rust, condensate corrosion, mineral deposit, bacteria)
- Highly recommended in every case and mandatory for the ASHP used in cooling mode : antifreeze treatment at -25°C
- **Optional**: Manometer for the end-user (in addition with the inside ASHP manometer)
- **For the separated DHW tank : 3/4" Isolated heating pipework between ASHP (OPTIM' DUO 4 or 6kW) and DHW tank**


#### Electric hardware parts procurement list and project recommendations

- Installation must be protected by a 30mA differential circuit breaker
- Installation of power cable 3G6 for 4 and 6kW 3G6 + 32 A breaker (curve D)
- Cabling between each thermostat and ASHP: 2 wires 9/10 and 2 wires 0,5mm<sup>2</sup> for the receptors (TYBOX and TH RA).
- **For the separated DHW tank version, installation of DHW temperature sensor: 1 pair of 9/10 wires (if DHW away more than 3 meters)**
- **For the separated water distribution version (unmixed zone) 2 ways valve connection: 2 wires 0.5mm<sup>2</sup>.**
- **For the separated water distribution version (mixed zone) 2 ways valve connection: 2 wires 0.5mm<sup>2</sup>, water pump : 3G1.5mm<sup>2</sup> power cable, 3 ways valve : 3G0,5mm<sup>2</sup>, and temperature sensor of the mixed zone : 1 pair 9/10 cable.**
- **For the mixing bottle installation, water pump installation: 3G1.5mm<sup>2</sup> power cabling, temperature sensor(s): 1 pair 9/10 wires and 3 ways valve: 3G0.5mm<sup>2</sup>**

- (1) At minimum 30% of the water flow, through the zone emitters = without head thermostatic radiator valves, motorized electro valve, actuator or other.
- (2) Mixing (buffer) bottle wall mounting of 25L for OPTIM-04M (diameter 320/height 800), of 50L for OPTIM-06M (diameter 375/height 1050) and of 80L for OPTIM-09M (diameter 480/hauteur 750).


## 2-1 Grid installation

### 1- LAY THE WOODEN BLOCKS



1. Lay the two wooden blocks 20 mm thick (provided with the grid) on the hole base of the wall.


### 2- INSTALL AND SECURE THE GRID INSIDE THE WALL



1. Put the grid on the two wooden blocks.
2. Make sure that the grid is horizontal and properly in contact with the wall surface. Then screw the mounting brackets on the wall with proper screws and screws anchor (not provided) see picture above).


## 2-2 Air duct installation

### 3- AIR DUCT FIXING




1. Install the air duct to the mounting brackets with 8 screws ISO ISO4017 M6\*20 and the M6 washers (provided with the air duct / see above picture).
2. Possibility to make the air tightness with rockwool by filling the space around the air duct. In case of PU expansive foam use, see the next step.

### 4- FRAME AIR DUCT FIXING




1. Screw the 4 frames part (screw not provided) in the air duct, make sure that they are properly in contact with the wall surface (3 screws / side frame parts and 2 screws / horizontal frame parts / see picture above ).
2. Finalize the air tightness with PU expansive foam. Specific holes are made in the frame part to inject the expansive foam.

5- ASHP ALIGNMENT AND POSITIONING




1. Use the ASHP adjustable foot to have the air duct straight to the hole in the wall.
2. Secure the ASHP to the air duct using the four handles (see picture above).

6- INSTALL THE TANK ON THE ASHP  
(ONLY FOR OPTIM'DUO 4 AND 6 KW)




1. Put the inlet / outlet of the tank at approximately 25° on the left of the ASHP, when you are in the front of the machine, in order to facilitate the hydraulic connections later. (see detail pict. page 13).

7- INSTALL THE TANK BODY PANELS  
(ONLY FOR OPTIM'DUO 4 AND 6 KW)




1. Secure the two side body panels with the provided bar, square and the 4 slotted flat screws head M6\*20 (see pictures above).
2. Lay the tank side panels you have just assembly, on the ASHP side panels body. Then, on the top of the front body panel (see zoom picture), screw the tank door panel in the fixing square with 2 screws DIN7991 M6\*40


8- OPTIM 9KW DOOR OPENNING





1. Pull in your direction the bottom panel where the arrows are shown in the diagram (no fixation screw)





2. Remove the panel



3. Remove the roof (no fixation screw)



4. Lift the first bolt located at the bottom of the back of the panel (see arrow in the diagram) then remove the panel at the bottom.
5. Do the same on the other side




6. Push the panel up to remove it


 See bolts on step 6 at the right.

2-4 Hydraulic connections

OPTIM 4 and 6




OPTIM 9 kW



**2-5 Electrics connections**

2-5-1 Connecting the power network



See « 2-5-1-2 THERMOSTAT CONNECTION BLOCKS »


PAC	Power : Electric ASHP	Power : Duo tank elec. heaters	Mixing tank version	Cabling ASHP- Thermostats
<b>OPTIM'DUO 4kW</b>	3G6 / breaker 32A (curve D)	3G1,5 (only 200L)	Water Pump: 3G1,5 DHW sensor: 1 pair 9/10 3 ways valve: 3G0,5	9/10
<b>OPTIM'DUO 6kW</b>	3G6 / breaker 32A (curve D)	3G1,5 (200 and 300L)	Water pump: 3G1,5 DHW sensor: 1 pair 9/10 3 ways valve: 3G0,5	9/10
<b>OPTIM'DUO 9kW</b>	3G6 / breaker 32A (curve D)	3G1,5 (200 and 300L)	Water pump: 3G1,5 DHW sensor: 1 pair 9/10 3 ways valve: 3G0,5	9/10

**See commissioning document for the values to register (see sample form at the end of the document).**


2-5-2 Sensor temperature connections

Connect the DHW temperature sensor (delivered with the tank) on the block N°80 and block B10 of the control board (see diagram below).

If separated water distribution with mixed zone, the temp. Sensor of the zone must be connected on the block N°80 and the block B8 of the control board (see diagram below).



2-5-3 Sub zone 2 ways valves connection and sub zone water pumps connection (water distribution separated from the ASHP)



If water distribution WITH Mixed zone(s) :

- zone 1 = zone mixed
- zone 2 = zone mixed or direct zone
- zone3 = zone direct


→ Full details: chapter 9 of « Technical Documentation ».

See 2 ways valves set-up in the ASHP control board page 21

2-5-4 Thermostats connection

2-5-4-1 TH FI

1. Connect Thermostat as diagram below



3. Remove the battery power storage protection

2. Remove the cover with a slotted screwdriver



See full details in the thermostat manufacturer manual.

2-5-4-2 TYBOX

1. Remove the thermostat cover with a slotted screw driver




2. Remove the battery power storage protection



3. Remove the block cover back to the receptor



4. Connect as diagram below



Install the receptor outside the ASHP OPTIM.


See full details in the thermostat manufacturer manual.

2-5-4-3 TH RA

2. Remove the block cover back to the receptor



2. Connect as diagram below



3. Remove the cover with a slotted screw driver



4. Remove the battery power storage protection



### 3- START-UP STEPS

N°	Start-ups steps
1	Power on the ASHP
2	Connect the thermostats
3	Manually check the 3 ways valve closing
4	Manually start the water pumps(s)
5	Purge water circuit
6	Test of water flow efficiency
7	Define ASHP water set point and set point
8	ASHP start running
9	Check input/output values
10	Heating demand test

***Water distribution 1 to 2 zones non mixed (P.21)***

***Water distribution 2 zones, included 1 mixed (P.27)***

3-0 ASHP Control panel & screen terminal function and mode



-  Compresseur is running
-  Defrost on going
-  Heatinge
-  Water pump is running
-  Domestic Hot Water production

Menu screen code meaning :



First character signification	
X...	
A	On/Off ASHP
B	Set point
C	Clock/Time program heating
D	Input/Output
E	Alarms history log
F	Board replacement
G	Assistance
H	Manufacturer

Example code Gg01 :

**G:** Assistance menu

**g:** Sub menu « gestion manuelle »

**01:** First screen of the sub menu « Gestion manuelle »

### 3-1 ASHP Power on

Place the switch and the breakers at « on »(E0, E1, E3 et E5)



### 3-2 TYBOX thermostat radio synchronization

- 1- Press the top button of the receptor during 3 seconds (The led must blink 3 times).
- 2- Press the thermostat « mode » and « + » buttons at the same time, during 3 secondes (screen: rF00).
- 3- Press 1 time, thermostat « + » button (screen: rF01).
- 4- Then press one more time on thermostat « mode » and « + » button to exit.

 See full details in the thermostat constructor manual.

### 3-2 The 2 Ways valves set-up and commissioning (sub-zone)



To access to the following menus:

Menu principal → Assistance → Param. Assistance → Thermoreg.


**1. Access Gfc55 menu: « Présence vanne V2V »**

If Sub-zone is controlled by a 2 ways valve (**separated from ASHP**) → select « OUI » to declare the V2V.

**2. Access Gfc56 menu: « Affectation V2V ? » for their assignment**


For each sub-zone (outside ASHP), select the water set point requested:

- Loi d'eau 1 = Lowest water set point = **mixed zone**
- Loi d'eau 2 = Highest temp. Water set point




WATER DISTRIBUTION 1 OR 2 ZONES DIRECTS		Page n°
1	Manually start the 3 and 2 ways valves	Page 20
2	Manually start the water pump	Page 21
3	Purge water circuit	Page 21
4	Test of water flow efficiency	Page 21 et 22
5	Define ASHP water set point and set point	Page 22
6	ASHP start running	Page 23
7	Check input/output values	Page 23
8	Heating demand test	Page 23

*Water distribution 1 zone direct :*




*Water distribution 2 zones direct (Integrated kit or not at the ASHP) :*




**3-3 Manual mode to purge the water circuit and test water flow efficiency: 1 à 3 zone(s) direct(s)**

 In case of alarm code, see the alarms code table (**annex page 34**)

3-3-1 Valves start



X



**1. Access to the main menu:**

Press « Programmation » button  to go to the main menu. Then press down arrow button  until menu « G.Assistance », then press enter  button to validate.

**2. Within the assistance menu :**

Press down arrow button  until « Gestion manuelle » menu. Then press enter  button to validate.

**3. Password : « 1234 »**

Press enter  button to have the cursor blinking of the first digit. Press up arrow  button until n° « 1 ». Press  enter button to validate the first digit. Do the same for the 3 last digits.

**4. Manual test of the valves (menu « Gestion manuelle »):**

Within the menu Gg08 :

- Press on  return button to have the cursor blinking on the « Y2 » value.
- Change to « Oui » and then modify the Y2 value from 0.0 V to **10.0V** by pressing the  up arrow. Then validate with « enter » button . Verify the 3 ways valve Y2 for DHW/heating is opening at 100% to the circuit A (=heating circuit)



Open up duration of the 3 ways valve is about = 60 sec

Within the Gg05 and Gg06 menu:


- Press on  enter to have the cursor blinking on the **Dout2** value.
- Change to « Oui » and change the value of **Dout2** at « 1 » (relay switched on / closed => on going valve opening) press  enter. Then validate, and press on . Verify that the 2 ways valve of zone 1, is opening slowly (the control metal rod in the middle of the actuator / Motor valve will come up, it takes approximatively 6 mm, to have the rod fully come up .
- Follow the same procedure with zone 2: **Dout6**.
- If 2 other 2 ways valves, follow the same procedure with **Dout9** and/or **Dout10** and/or **Dout11**



Open up duration of the 2 ways valve is about = **360 sec => 6 minutes**

- **When all of the valves are fully open, go to step 5. Otherwise check cabling.**

3-3-2 ASHP Water pump start



5. Within the Gg01 menu (Gestion manuelle):

- Press on To have the blinking cursor on AUT (see photo)
- Press on to have «Pompe primaire» in **MAN** (manual).  
Press on to validate.



Wait for the water pump front panel green led switch on, then go to step 6.

3-3-3 Test of water flow efficiency and water circuit purge

Control that the ASHP water pump is on number « 8 », in « débit constant » mode (constant flow).



**CAUTION** : The ASHP water pump is running at « débit constant » (constant flow) and not at « pression constante. » (constant pressure)



6. Within the D07 (Entrées/Sorties) menu :


Water flow test: All of the valves are open and the water pump is started and running

- **Manually shut the differential pressure valve as far as possible** by screwing clockwise (see photo).
- **Purge the water circuit.**
- **Check flow within D07 menu D07** ( = flow ok / = flow not ok ) :
  - If → open differential pressure valve until reach the correct water flow.
  - If → water flow OK, go to next step.



Example: Water distribution 2 zones direct:

Alternate the demand for each zone (Dout2 → valve zone 1, Dout6 → valve zone 2), **only one zone open at the same time.**



- **Shut off the valve Dout6 (see step 4).** When the valve is completely shut (360sec), **verify the flow** within the menu D07 as above:
  - If → Open differential pressure valve until reach the correct water flow.
  - If → Water flow ok, go to next step.

- **Open Dout6 valve and shut off valve Dout2.**  
When the valve is completely shut (360sec), **verify the flow** within menu D07 as above:
  - If  → Open differential pressure valve until reach the correct water flow.
  - Si  → Water flow is ok, go to next step.
- **Close Dout6 and switch Y2 on the DHW circuit with the value 0.0V** (step 4) In order to have a water circulation in the DHW tank hot water coil and so purge it.



**Caution:** In case of sub zone commissioning, open each zone one by one and adjust the differential pressure valve in relation with the water flow. (same approach than above)


- **Within Gg01 menu → set-up back « pompe primaire » in AUT.**
- **Within Gg06 menu → set-up back Dout9, Dout10 and Dout11 at « NON »** (Cancel the relay switched / forced at on) and **«  »**
- **Within Gg08 menu → set-up back the Y2 valve at 0.0V et validate « NON »** (Cancel the Y2 switch to DHW circuit) and **«  »**



### 3-3-4 Water set point and set point adjustment

#### 7. Within Ha04-2 menu


Set-up value « Oui » to « Gestion des Lois d'eau » by zone and set-up « ToR » if there is a 2 ways valve or set up « 0-10V » if there is a 3 ways valves installed.



#### 8. Within Gfc52 et Gfc53 menus (Thermorégulation)

Possibility to adjust two water set point:


- « Loi d'eau 1 » → Water set point for the mixed zone (the lowest water set point)
- « Loi d'eau 2 » → Water set point **NOT** mixed (Highest water temp. as radiators emitter)




#### 9. Within B01 menu (Thermorégulation Unité)

Define the nominal set points:

- Refroidissement = Cooling: 15 °C
- Chauffage = Heating: 50 °C (Heating set point if no thermostat, otherwise the set point calculated from the water set point)
- Sanitaire = DHW: For testing purpose set-up a set point at 5°C above the DHW current temperature (Temp. given by the ECS sensor, see menu D02).




3-3-5 Temperature sensors start and control



**10. Within A01 menu « Mar/Arr Unité» (On/Off ASHP)**

Start the ASHP:

Set-up parameters at « Chaud + ECS » and « Marche »



**11. Within the D menu (Input/Output)**

After several minutes of ASHP running, control all of temperature sensors value and their accuracy:

Menu D01: B1 Water input / B2 output temp. sensors.

Menu D02: B10 DHW temp. sensor ECS.

Menu D03: B3 Outdoor temp. sensor and B4 Discharge output compressor.

Menu D04: B5 Compressor suction temp., B6 HP High pressure and B7 BP Low pressure.

**11. Heating demand test**

When the DHW set point temporary test is reach, create a demand in the heating zone 1 with the thermostat. Control that the heating zone temp. match the demand zone temp., otherwise control the thermostats cabling. For that, see P.13 to P.15 and/or the hydraulic connection. If the heating zone match the set point demand zone, do the same test with zone 2 and zone 3.

When validated, st-up the Domestic Hot Water set point within the B01 field following the chart below.


ASHP	150L Tank	200L Tank	300L Tank
<b>OPTIM'DUO 4kW</b>	55°C maxi	55°C maxi	/
<b>OPTIM'DUO 6kW</b>	50°C maxi	55°C maxi	55°C maxi



**FILL THE COMMISSIONING PROCEDURE FORM WITH COLLECTED RELEVANT DATA**


N°	WATER DISTRIBUTION 2 ZONES, INCLUDING 1 MIXED	Page n°
1	Manually start the 3 and 2 ways valves	Page 25
2	Manually start the water pump	Page 26
3	Purge water circuit	Page 26
4	Test of water flow efficiency	Page 26 et 27
5	Define ASHP water set point and set point	Page 27
6	ASHP start running	Page 27
7	Check input/output values	Page 28
8	Heating demand test	Page 28

*Water distribution 2 zones direct, including 1 mixed (Water distribution kit integrated or not to the ASHP):*



**3-4 Manual start to purge the water circuit and test of water flow efficiency: 2 ou 3 zones including 1 or 2 mixed**

3-4-1 Manually start the 3 and 2 ways valves



**1. Access to the main menu:**

Press on the « Programmation » button  to go to the main menu.  
Then press down arrow button until  « G.Assistance », Then validate with the enter button .

**2. Within the « assistance » menu :**

Press down  arrow button until « Gestion manuelle». Then validate with enter button .

**3. Password: 1234**

Press on  enter button to have the cursor blinking on the first digit  
Then press on  arrow up until « 1 », validate with  enter button.  
After the first digit repeat the same way for the 3 last digits.

**4. Valves manual test within « Gestion manuelle » menu:**

Within Gg08 menu :




- Press enter  button, to have the cursor blinking on the Y2 value.
- Change from « Non » to « Oui » and modify Y2 « Valeur » with arrow up  button, to **10.0 V**. **Validate with  enter button.** Verify that the 3 ways valve Y2 for DHW/heating is opening at 100% towards the A circuit (=> heating circuit)
- Follow the same procedure with Y3 valve (100% open = not mixed, 0%=closed. Loop on the heating circuit).



Open up duration of the 3 ways valve is about = 60 sec

Within Gg05 and Gg06 menu:




- Press return  button to have the value Dout6 blinking.
- Change from « Non » to « Oui » and modify the **Dout6** value at open valve activated by changing the blank box  to the black box  by pressing on the arrow up  button. Validate with the  enter button.
- Verify that the 2 ways valve of zone 1, is opening slowly (the control metal rod in the middle of the actuator / motor of the valve will come up in approximatively 6mn).  
Follow the same procedure if 2 extra valves installed **Dout9** and/or **Dout10** and/or **Dout11**



Open up duration of the 2 ways valve is about = 360 sec => 6 minutes

- **As far all of the valves are fully open, then go to step 5.**

3-4-2 Water pumps start



5. Within Gg01 (Gestion manuelle) menu:

- Press on To have the cursor blinking on AUT (see photo)
- Press to have «Pompe primaire» in « MAN » (manuelle) and validate with
- Then in the menu « gestion manuelle Gg05 » set-up « Dout2 » at « Oui » and validate the value (the box must be black) to switch on the water pump of the mixed zone.




Control that the water pumps are running. If OK, go to step 6.

3-4-3 Test of water flow efficiency, and circuit purge

Control that the ASHP water pump is set-up at number « 8 », in « débit constant » mode (constant flow).




**CAUTION:** The ASHP water pump is running at « débit constant » (constant flow) and not at « pression constante. » (constant pressure)






7. Within the « Entrées/Sorties » D07 menu:

Water flow test: All of the valves are open and the water pump is started and running

- Manually shut the differential pressure valve as far as possible by screwing clockwise(see photo).
- Purge the water circuit.
- Check flow within D07 menu,03Ctrl. Débit( =flow ok / = flow not ok):
  - If → open differential pressure valve until reach the correct water flow.
  - If → water flow OK, go to next step.



Alternate the demand on the zones (Dout2 → water pump zone 1, Dout6 → valve zone 2), **Only one zone valve open at the same time.**






- **Shut valve Dout6 (see step 4).** When the valve is fully shut (360secs), control the water flow in the D07 menu like above:
  - If  → Open differential pressure valve, until reach the correct water flow.
  - Si  → Water flow is ok, go to next step.
- **Open valve Dout6 and stop water pump Dout2.** When the water pump is OFF, control the water flow on D07 menu as before :
  - If  → Open differential pressure valve until reach the correct water flow.
  - Si  → Water flow is ok, go to next step.
- **Shut valve Dout6 and open Y2 on the DHW circuit with set-up 0.0V** (setp 4) In order to make water running thru the tank coil and so purge it.



**Caution:** In case of sub zone commissioning, open each zone one by one and adjust the differential pressure valve in relation with the water flow. (same approach than above)

- Within Gg01 menu → « pompe primaire » menu, set-up « AUT ».
- Within Gg06 menu → set-up at « Non », Dout9, Dout10 and Dout11 (Cancel the relay switched / forced at on) and have a blank box «  » back again
- Within Gg08 menu → set-up back at 0.0V the Y2 valve and validate « Non » (Cancel the Y2 switch to DHW circuit) and have the box blank «  »

3-4-4 Define water set points and set points



7. Within Ha04-2 menu


Set up « Oui » to the water set point field « gestion loi d'eau » and « ToR » if it is a 2 ways valves or « 0-10V » if it is a 3 ways valve

8. Within Gfc52 et Gfc53 menu (Thermorégulation)

Possibility to adjust two water set point:

« Loi d'eau 1 » → Water set point for the mixed zone (the lowest water set point)

« Loi d'eau 2 » → Water set point **NOT** mixed (Highest temp. water like for radiators)




**10. Within B01 menu (Thermorégulation Unité)**

Define the nominal set point:

- Refroidissement = Cooling : 15 °C
- Chauffage = Heating: 50 °C (Heating set point if no thermostat, otherwise the set point is calculated from the water set point)
- Sanitaire = DHW: For testing purpose put the set point at 5°C above the DHW current temperature (Temp. Given by the ECS sensor, menu D02).


3-4-5 Temperature sensors start and control



**11. Within A01 menu « Mar/Arr Unité »(On/Off ASHP)**

Start the ASHP:

Set-up select « Marche » et « Chaud + ECS »



**12. Within the D menu (Input/Output)**

After several minutes of ASHP running, control all of temperature sensors value and their accuracy:

Menu D01: Water input / output temp. sensors.

Menu D02: DHW temp. sensor ECS.

Menu D03: Outdoor temp. sensor and Discharge output compressor.

Menu D04: Compressor suction temp., HP High pressure and BP Low pressure.

**13. Heating demand test**

When the DHW set point temporary test is reach, request a demand in the heating zone 1 with the thermostat. Control that the heating zone temp. match the demand zone, otherwise Control the thermostats cabling. For that, see P.13 to P.18 and/or the hydraulic connections. If the heating zone match the set point demand zone, do the same test with zone 2.

When it is validated, put but the Domestic Hot Water set point within the B01 field following the chart below.

ASHP	150L Tank	200L Tank	300L Tank
<b>OPTIM'DUO 4kW</b>	55°C maxi	55°C maxi	/
<b>OPTIM'DUO 6kW</b>	50°C maxi	55°C maxi	55°C maxi



**FILL THE COMMISSIONING PROCEDURE FORM WITH COLLECTED DATA**

## ANNEX : COMMISSIONING AND ACCEPTANCE DOCUMENT

											
ASHP OPTIM COMMISSIONING DOC.											
Arriving time :						Départure time :					
ASHP MODEL :				SERIAL NUMBER :				DATE :			
Installer name and address :						Owner name and address :					
HEATING AREA ZONE ( if it exists)						H1	H2	H3			
Difference of input - Output T° (Winter)=											
<b>1) BREAKER PROTECTION</b>											
Type =						Caliber =					
<b>2) ELEC. POWER NETWORK</b>											
Ph1/N =				Ph2/N =				Ph3/N =			
Ph1/Ph2 =				Ph2/Ph3 =				Ph1/Ph3 =			
<b>3) COMPRESSOR</b>											
Low Pressure	b	°C	High Pressure	b	°C						
Ha 14*	T°ext min		T°ext max		Mini. speed				Max speed		
Ha 15*	T°ext min		T°ext max		Mini. speed				Max speed		
Ha 16*	T°ext min		T°ext max		Mini. speed				Max speed		
<b>4) EXPANSION VALVE</b>											
Open %		SHR °K		High Pres. °T		Low Pres.°T					
<b>5) FAN</b>											
Voltage		% Speed		Current							
<b>6) WATER PUMP</b>											
Voltage		Speed setup		Current							
- TEMPERATURE MANAGEMENT -											
SOFT Version =				THERMOSTAT version =				THERMOSTAT RADIO Vers.=			
Delta T water (winter)=						Delta water (summer)=					
<b>1) ZONE 1 - Water set point Gfc 52*</b>											
T° ext mini =						Water T° INPUT min =					
T° ext maxi =						Water T° OUTPUT max =					
<b>2) ZONE 2 - WATER SET POINT Gfc 53*</b>											
T° ext mini =						Water T° INPUT min =					
T° ext maxi =						Water T° OUTPUT max =					
<b>3) OUTDOOR TEMPERATURE</b>						Outdoor T° =					
- WATER CIRCUIT -											
<b>1) WATER &amp; CIRCUIT PURGE</b>											
Lenght & intern. Diam. Pipework (if tank) - mm =						Antifreeze rate (Y/N) = %					
Number of hydraulic heating zones =						Buffer tank volume =					
Water pump is poerating : <input type="checkbox"/>						V3V Valve DHW /Home heating is ops. : <input type="checkbox"/>					
DHW Option (Yes / No) =											
AMZAIR Industrie 521, rue Gustave Eiffel ZA Penhoat 29860 PLABENNEC (France)						Procédure IE054					
Tél. +33 (0)2 98 38 42 50 - Fax. : 42 54 - contact@amzair.eu - www.amzair.eu						Version 2.1 ; 01 / 09 / 2016					
This document is a property of Amzair Industrie and cannot be copied or reused without the formal authorization of Amzair Industrie. It can be subject to change without notification. DOCUMENT ET PICTURES ARE NOT CONTRACTUAL – 2018/06/10											

- HYDRAULIC CIRCUIT -			
<b>2) SENSORS COMMISSIONNING AND TEMPERATURES CONTROL</b>			
<b>Domestic Hot Water</b>			
Recorded after 15 minutes in operation			
T° ext =	Output T° ASHP =	Input T° ASHP =	DHW tank T° =
<b>Heating zone 1 (CC1)</b>			
Emitters type	Heating floor	Radiators	Fan coil unit
V3V valve Zone 1 in operation checking : <input type="checkbox"/>		Water pump zone 1 in operation checking : <input type="checkbox"/>	
Recorded after 15 minutes in operation			
T° ext =	Output T° ASHP =	Buffer tank T° =	Output T° CC1 (ctrlr) =
Input T° ASHP =	Ambient T° zone 1 =	Output T° CC1 (thermometer) =	Input T° CC1 (thermometer) =
<b>Heating zone 2 (CC2)</b>			
Emitters type	Heating floor	Radiators	Fan coil unit
V3V valve Zone 2 in operation checking : <input type="checkbox"/>		Water pump zone 2 in operation checking : <input type="checkbox"/>	
Recorded after 15 minutes in operation			
T° ext =	Output T° ASHP =	Buffer tank T° =	Output T° CC2 (ctrlr) =
T° retour PAC =	Ambient T° zone 1 =	Output T° CC2 (thermometer) =	Input T° CC2 (thermometer) =
<b>3) ASHP INPUT/OUTPUT TEMPERATURE</b>			
*			
ASHP Output T° =	Input T° ASHP =	Water pump speed set-up :	
<b>COMMENTS :</b>			
* : To be extract from the controler			
<u>ENGINEER NAME :</u>		<u>OWNER NAME :</u>	
<u>ENGINEER SIGNATURE :</u>		<u>OWNER SIGNATURE :</u>	
<b>Amzair Indus. commissioning document approval field</b>			
CONFORM <input type="checkbox"/>		NOT CONFORM <input type="checkbox"/>	
<u>Name and signature :</u>		<u>Cie stamp :</u>	
"AMZAIR Industrie 521, rue Gustave Eiffel ZA Penhoat 29860 PLABENNEC (France) Tél. +33 (0)2 98 38 42 50 - Fax. : 42 54 - contact@amzair.eu - www.amzair.eu"		Procedure IE054 Version 2.1 ; 01 / 09 / 2016	
This document is a property of Amzair Industrie and cannot be copied or reused without the formal authorization of Amzair Industrie. It can be subject to change without notification. DOCUMENT ET PICTURES ARE NOT CONTRACTUAL – 2018/06/10			

## ANNEX : ALARMS CODE TABLE

Alarm Code	Alarm cause
<b>ALA01</b>	ASHP input temperature sensor (B01) failure or disconnected
<b>ALA02</b>	ASHP output temperature sensor (B02) failure or disconnected
<b>ALA03</b>	Outdoor ASHP temperature sensor (B03) failure or disconnected
<b>ALA04</b>	Compressor discharge temperature sensor (B04) failure or disconnected
<b>ALA05</b>	compressor suction temperature sensor (B05) failure or disconnected
<b>ALA06</b>	HP / High pressure sensor (B06) failure or disconnected
<b>ALA07</b>	BP / Low pressure sensor (B07) failure or disconnected
<b>ALA08</b>	Zone 1 output temperature sensor (B08) failure or disconnected
<b>ALA09</b>	Zone 2 output temperature sensor (B09) failure or disconnected
<b>ALA010</b>	DHW - ECS - Temperature sensor (B10) failure or disconnected
<b>ALP03</b>	ID03: Flow switch ASHP water primary circuit → water flow to weak



# AMZAIR

monobloc premium heat pumps



## AMZAIR Industrie SAS

Office, Factory, and show-room at 5 min from the Brest airport

ZI de Penhoat - 521, rue Gustave Eiffel - 29860 PLABENNEC ( France)

[www.amzair.eu](http://www.amzair.eu) - Tél : 33 (0)2 98 38 42 50 - Fax : 33 (0)2 98 38 42 54 - [contact@amzair.eu](mailto:contact@amzair.eu)